



1

00:00:05,240 --> 00:00:10,340

Preparing the Orion crew module for its first flight test in December actually began a few

2

00:00:10,340 --> 00:00:16,250

years ago. The crew module for Orion's flight test arrived at Kennedy Space Center in Florida

3

00:00:16,250 --> 00:00:22,000

in June 2012 and was transported to the Neil Armstrong Operations and Checkout Building

4

00:00:22,000 --> 00:00:26,520

high bay for manufacturing, processing and preflight testing.

5

00:00:26,520 --> 00:00:32,960

During the next two years, Orion prime contractor Lockheed Martin and NASA engineers and technicians

6

00:00:32,970 --> 00:00:38,650

built-up the crew module from a green shell to a fully functional spacecraft. Many tests

7

00:00:38,650 --> 00:00:42,470

were performed to prepare Orion for its flight test.

8

00:00:42,470 --> 00:00:47,360

Orion's service module arrived at Kennedy Space Center and also was transported to the

9

00:00:47,360 --> 00:00:53,070

Operations and Checkout Building for build-up and processing. The module was completed with

10

00:00:53,070 --> 00:00:58,030

the installation of the fairings that protect it in the early stages of launch ascent.

11
00:00:58,030 --> 00:01:03,320
Orion's heat shield, containing more than 200 instrumentation sensors, was installed.

12
00:01:03,320 --> 00:01:08,470
The heat shield will protect Orion during its re-entry into Earth's atmosphere and splashdown

13
00:01:08,470 --> 00:01:10,920
in the Pacific Ocean.

14
00:01:10,920 --> 00:01:15,200
Moving one step closer to the flight test, the Orion Crew Module was stacked atop the

15
00:01:15,200 --> 00:01:20,770
Service Module in June. Tile panels were installed around the spacecraft and then

16
00:01:20,770 --> 00:01:24,780
both modules were put through their final system tests.

17
00:01:24,780 --> 00:01:30,229
On Sept. 11, the Orion stack was transported from the Operations and Checkout Building

18
00:01:30,229 --> 00:01:35,729
to the Payload Hazardous Servicing Facility. Inside this facility, the spacecraft was fueled

19
00:01:35,729 --> 00:01:41,130
with ammonia, hydrazine and high-pressure helium ahead of its December flight test.

20
00:01:41,130 --> 00:01:46,640
The four major components for Orion's Launch Abort System, including the launch abort motor

21

00:01:46,640 --> 00:01:51,389

and the attitude control motor, arrived at Kennedy last year and were transported to

22

00:01:51,389 --> 00:01:57,159

the Launch Abort System Facility for processing, testing and integration.

23

00:01:57,159 --> 00:02:02,350

In late September, Orion was moved from the Payload Hazardous Servicing Facility to the

24

00:02:02,350 --> 00:02:04,880

Launch Abort System Facility.

25

00:02:04,880 --> 00:02:09,890

Inside the high bay, the Launch Abort System was lowered and attached to Orion. The system

26

00:02:09,890 --> 00:02:15,360

is designed to protect astronauts if a problem arises during launch by pulling the spacecraft

27

00:02:15,360 --> 00:02:21,180

away from the falling rocket. Orion waited inside the Launch Abort System Facility until

28

00:02:21,180 --> 00:02:27,560

the United Launch Alliance Delta IV Heavy rocket was ready for integration with the spacecraft.

29

00:02:27,560 --> 00:02:33,920

Earlier this year, the Delta IV core and starboard boosters arrived by barge in March, and were

30

00:02:33,920 --> 00:02:39,230

offloaded and transported to the Horizontal Integration Facility near Space Launch Complex

31

00:02:39,230 --> 00:02:45,220

37 at Cape Canaveral Air Force Station in Florida. The port booster and second stage

32

00:02:45,220 --> 00:02:47,500

followed in early May.

33

00:02:47,500 --> 00:02:52,450

The Delta IV central core booster was mated to the port and starboard boosters. Then the

34

00:02:52,450 --> 00:02:57,140

Delta IV second stage was mated to the rocket's central core booster.

35

00:02:57,140 --> 00:03:01,900

The Delta IV rocket for Orion's flight test rolled out of the Horizontal Integration Facility

36

00:03:01,900 --> 00:03:05,560

on Sept. 30 and made the trek to the launch pad.

37

00:03:05,560 --> 00:03:12,450

In the early morning on Oct. 1, the nearly 180-foot-tall launch vehicle was carefully

38

00:03:12,450 --> 00:03:18,380

lifted into the vertical position and then raised into the Mobile Service Tower on the pad.

39

00:03:18,380 --> 00:03:24,870

In early November, the Orion stack was transported to the launch pad and integrated to the rocket.

40

00:03:24,870 --> 00:03:31,470

Tests were performed to verify readiness for launch. After more than two years of work,